

TABELA ROBÓT ZIEMNYCH

Pikieta	Powierzchnia		Powierzchnia średnia		Odległość	Objętość		Zużycie na miejscu	Nadmiar objętości		Suma algebraiczna	
	Wykop	Nasyp	Wykop	Nasyp		Wykop	Nasyp		Wykop	Nasyp	Wykop	Nasyp
	m <sup>2</sup>		m <sup>2</sup>			m	m3		m <sup>3</sup>	m3		m3
1	2	3	4	5	6	7	8	9	10	11	12	13
10.40	2.1	0.0										
13.40	2.1	0.0	2.1	0.0	3.00	6.30	0.00	0.00	6.30	0.00	6.30	0.00
40.90	1.8	0.1	1.9	0.0	27.50	53.08	1.10	1.10	51.98	0.00	58.28	0.00
66.80	1.7	0.1	1.7	0.1	25.90	44.29	1.81	1.81	42.48	0.00	100.75	0.00
84.10	1.8	0.0	1.7	0.1	17.30	29.76	0.87	0.87	28.89	0.00	129.64	0.00
107.00	2.3	0.0	2.1	0.0	22.90	47.06	0.57	0.57	46.49	0.00	176.13	0.00
124.70	2.4	0.0	2.4	0.0	17.70	41.86	0.09	0.09	41.77	0.00	217.90	0.00
144.90	2.6	0.0	2.5	0.0	20.20	50.90	0.00	0.00	50.90	0.00	268.81	0.00
161.30	3.2	0.0	2.9	0.0	16.40	47.48	0.00	0.00	47.48	0.00	316.28	0.00
175.30	3.7	0.0	3.4	0.0	14.00	48.02	0.00	0.00	48.02	0.00	364.30	0.00
197.60	2.8	0.0	3.3	0.0	22.30	72.70	0.11	0.11	72.59	0.00	436.89	0.00
225.30	2.8	0.0	2.8	0.0	27.70	78.11	0.14	0.14	77.98	0.00	514.87	0.00
261.50	2.8	0.0	2.8	0.0	36.20	101.36	0.00	0.00	101.36	0.00	616.23	0.00
276.10	2.8	0.0	2.8	0.0	14.60	40.44	0.00	0.00	40.44	0.00	656.67	0.00
300.10	2.5	0.0	2.6	0.0	24.00	63.12	0.12	0.12	63.00	0.00	719.67	0.00
326.00	2.2	0.0	2.4	0.0	25.90	60.99	0.39	0.39	60.61	0.00	780.27	0.00
347.70	3.4	0.0	2.8	0.0	21.70	61.30	0.43	0.43	60.87	0.00	841.14	0.00
371.30	2.4	0.1	2.9	0.0	23.60	68.20	0.94	0.94	67.26	0.00	908.40	0.00
394.60	2.9	0.1	2.6	0.1	23.30	61.05	1.28	1.28	59.76	0.00	968.17	0.00
418.40	3.7	0.0	3.3	0.0	23.80	78.66	0.59	0.59	78.06	0.00	1046.23	0.00
445.80	2.7	0.0	3.2	0.0	27.40	88.09	0.55	0.55	87.54	0.00	1133.77	0.00
469.00	2.4	0.0	2.5	0.0	23.20	58.93	0.58	0.58	58.35	0.00	1192.12	0.00
494.00	2.5	0.0	2.5	0.0	25.00	61.38	0.38	0.38	61.00	0.00	1253.12	0.00
517.10	3.2	0.0	2.9	0.0	23.10	66.76	0.35	0.35	66.41	0.00	1319.53	0.00
540.10	3.7	0.0	3.5	0.0	23.00	79.58	0.12	0.12	79.47	0.00	1399.00	0.00
564.80	3.2	0.0	3.5	0.0	24.70	85.34	0.00	0.00	85.34	0.00	1484.34	0.00
590.80	2.7	0.0	3.0	0.0	26.00	76.83	0.52	0.52	76.31	0.00	1560.65	0.00
613.50	2.2	0.0	2.5	0.0	22.70	55.84	0.91	0.91	54.93	0.00	1615.58	0.00
637.40	3.0	0.0	2.6	0.0	23.90	62.50	0.48	0.48	62.02	0.00	1677.60	0.00
656.50	3.5	0.0	3.3	0.0	19.10	62.36	0.00	0.00	62.36	0.00	1739.96	0.00
680.10	4.1	0.0	3.8	0.0	23.60	89.68	0.00	0.00	89.68	0.00	1829.64	0.00
703.20	2.9	0.0	3.5	0.0	23.10	80.39	0.00	0.00	80.39	0.00	1910.03	0.00
727.30	2.7	0.0	2.8	0.0	24.10	67.60	0.36	0.36	67.24	0.00	1977.27	0.00
752.00	2.1	0.1	2.4	0.1	24.70	59.65	1.98	1.98	57.67	0.00	2034.94	0.00
778.30	2.4	0.0	2.3	0.1	26.30	59.83	2.24	2.24	57.60	0.00	2092.54	0.00
			2.6	0.0	23.30	61.40	0.58	0.58	60.81	0.00		

801.60	2.8	0.0									2153.35	0.00
			3.1	0.0	25.30	79.32	0.13	0.13	79.19	0.00		
826.90	3.4	0.0									2232.54	0.00
			3.2	0.0	24.50	79.14	0.25	0.25	78.89	0.00		
851.40	3.0	0.0									2311.43	0.00
			3.0	0.0	22.80	68.63	0.34	0.34	68.29	0.00		
874.20	3.0	0.0									2379.72	0.00
			3.1	0.0	24.70	76.32	0.12	0.12	76.20	0.00		
898.90	3.2	0.0									2455.92	0.00
			3.2	0.0	19.50	62.01	0.10	0.10	61.91	0.00		
918.40	3.2	0.0									2517.83	0.00
			2.7	0.0	49.60	134.91	2.23	2.23	132.68	0.00		
968.00	2.3	0.1									2650.51	0.00
			2.4	0.1	23.10	56.48	1.50	1.50	54.98	0.00		
991.10	2.6	0.1									2705.49	0.00
			2.6	0.0	26.50	69.70	0.66	0.66	69.03	0.00		
1017.60	2.6	0.0									2774.52	0.00
			2.5	0.0	20.40	51.20	0.00	0.00	51.20	0.00		
1038.00	2.4	0.0									2825.73	0.00
			2.5	0.0	13.30	32.98	0.00	0.00	32.98	0.00		
1051.30	2.6	0.0									2858.71	0.00
			2.7	0.0	9.50	26.03	0.00	0.00	26.03	0.00		
1060.80	2.9	0.0									2884.74	0.00
			3.4	0.0	25.60	86.78	0.00	0.00	86.78	0.00		
1086.40	3.9	0.0									2971.52	0.00
			3.6	0.0	21.40	77.47	0.96	0.96	76.50	0.00		
1107.80	3.4	0.1									3048.03	0.00
			2.4	0.0	20.90	50.68	0.94	0.94	49.74	0.00		
1128.70	1.5	0.0									3097.77	0.00
			1.5	0.0	0.30	0.45	0.00	0.00	0.45	0.00		
1129.00	1.5	0.0									3098.22	0.00

RAZEM:	3122.93	24.71	24.71	3098.22	0.00
	A	B	C	D	E

Pikiet	Długość zdejmowanego humusu na przekroju	Długość robieranej konstrukcji na przekroju	Długości średnie dla odcinka humus	Odległość	Pole powierzchni humus	Suma algebraiczna
	m	m	m		m2	m2
1	2	3	4	6	7	9
10.40	0.0	9.0	0.0	3.00	0.00	0.00
13.40	0.0	9.0	0.8	27.50	20.63	
40.90	1.5	7.4	1.7	25.90	43.38	
66.80	1.9	7.1				64.01

66.80	1.9	7.1	1.9	17.30	33.04	97.05
84.10	2.0	7.2	3.0	22.90	69.04	
107.00	4.1	5.0	4.5	17.70	78.94	166.09
124.70	4.9	4.2	4.7	20.20	95.85	245.04
144.90	4.6	4.5	4.7	16.40	76.59	340.89
161.30	4.7	4.6	4.6	14.00	64.40	417.47
175.30	4.5	5.0	4.4	22.30	97.67	481.87
197.60	4.3	4.8	4.4	27.70	121.33	579.55
225.30	4.5	4.6	4.6	36.20	167.43	700.87
261.50	4.8	4.3	4.6	14.60	67.09	868.30
276.10	4.4	4.6	4.7	24.00	112.08	935.39
300.10	4.9	4.2	5.0	25.90	128.59	1047.47
326.00	5.0	4.2	4.8	21.70	104.27	1176.06
347.70	4.6	4.8	4.5	23.60	105.85	1280.33
371.30	4.4	5.0	4.3	23.30	101.24	1386.17
394.60	4.3	5.1	4.3	23.80	102.58	1487.41
418.40	4.3	4.8	4.6	27.40	125.90	1589.99
445.80	4.9	4.6	4.7	23.20	108.00	1715.89
469.00	4.4	4.7	4.5	25.00	113.63	1823.89
494.00	4.7	4.6	4.7	23.10	107.99	1937.51
517.10	4.7	4.4	4.6	23.00	105.34	2045.51
540.10	4.5	4.6	4.4	24.70	108.68	2150.85
564.80	4.3	4.7	4.7	26.00	122.46	2259.53
590.80	5.1	4.4	5.0	22.70	112.82	2381.99
613.50	4.9	4.6	4.9	23.90	116.87	2494.81
637.40	4.9	4.1	4.9	19.10	94.35	2611.68
656.50	5.0	4.1	4.9	23.60	114.70	2706.03
680.10	4.8	4.7	4.7	23.10	109.61	2820.73

703.20	4.7	4.3				2930.34
727.30	4.5	4.9	4.6	24.10	110.98	3041.32
752.00	5.8	3.8	5.2	24.70	127.58	3168.89
778.30	5.3	4.2	5.6	26.30	146.10	3314.99
801.60	4.4	4.8	4.8	23.30	112.42	3427.41
826.90	4.6	4.6	4.5	25.30	113.47	3540.88
851.40	5.0	4.3	4.8	24.50	117.48	3658.36
874.20	5.1	4.1	5.1	22.80	115.48	3773.84
898.90	5.3	3.9	5.2	24.70	128.93	3902.77
918.40	5.0	4.3	5.2	19.50	100.72	4003.49
968.00	6.0	3.7	5.5	49.60	273.30	4276.79
991.10	5.6	3.8	5.8	23.10	134.33	4411.11
1017.60	3.7	3.6	4.7	26.50	123.76	4534.87
1038.00	4.5	3.8	4.1	20.40	83.33	4618.20
1051.30	4.5	3.7	4.5	13.30	59.58	4677.79
1060.80	3.8	3.6	4.2	9.50	39.47	4717.26
1086.40	4.2	3.6	4.0	25.60	102.27	4819.53
1107.80	5.5	3.6	4.8	21.40	103.68	4923.22
1128.70	0.8	3.5	3.1	20.90	65.73	4988.95
1129.00	0.8	3.5	0.8	0.30	0.23	4989.18

zdejmowany  
humus:  
Łącznie 4989.18

TABELA ROBÓT ZIEMNYCH  
BUDOWA PARKINGU

Pikieta	Powierzchnia		Powierzchnia średnia		Odległość	Objętość		Zużycie na miejscu	Nadmiar objętości		Suma algebraiczna	
	Wykop	Nasyp	Wykop	Nasyp		Wykop	Nasyp		Wykop	Nasyp	Wykop	Nasyp
	m <sup>2</sup>		m <sup>2</sup>			m	m3		m <sup>3</sup>	m3		m3
1	2	3	4	5	6	7	8	9	10	11	12	13
0.00	11.2	1.3	8.7	1.9	7.72	66.78	14.67	14.67	52.11	0.00		
7.72	6.1	2.5									52.11	0.00
13.80	5.2	1.5									74.30	0.00
RAZEM:						101.13	26.83	26.83	74.30	0.00		