

PRZEDMIAR ROBÓT

[illegible]

PRZEDMIAR ROBÓT

Lp.	Podsta- wa	Opis i wyliczenia	j.m.	Poszcz	Razem
14 d.3.2	KNNR 6 1003-02	Powierzchniowe utrwalanie nawierzchni z podwójnym rozsypaniem grysów kamiennych o wym. 5-8 mm wg obmiaru: 13,50*1,80 = 25,11m2 40,50*1,30 = 55,08 m2 32,00*2,00 = 65,92m2 31,00*1,50= 48,36 m2 7,00*1,60 = 11,62 m2 18,00*2,00 = 37,08 m2 41,50*5,00 = 212,48 m2 13,50*1,80= 25,11 m2 16,50*1,80 = 30,69 m2 24,50*2,50 = 62,72 m2 30,00*2,00 = 61,80 m2 Razem 617,40 m2 617.00	m ²		
			m ²	617.000	
				RAZEM	617.000
15 d.3.2	KNNR 6 1003-01	Powierzchniowe utrwalanie nawierzchni z podwójnym rozsypaniem grysów kamiennych o wym. 2-5 mm wg obmiaru: 13,50*1,80 = 25,11m2 40,50*1,30 = 55,08 m2 32,00*2,00 = 65,92m2 31,00*1,50= 48,36 m2 7,00*1,60 = 11,62 m2 18,00*2,00 = 37,08 m2 41,50*5,00 = 212,48 m2 13,50*1,80= 25,11 m2 16,50*1,80 = 30,69 m2 24,50*2,50 = 62,72 m2 30,00*2,00 = 61,80 m2 Razem 617,40 m2 617.00	m ²		
			m ²	617.000	
				RAZEM	617.000